



Interreg 
North-West Europe
H2SHIPS



H2 Refuelling Station

2023.06.29

About Port Oostende

- In just over ten years, Port Oostende has become a major hub for the offshore wind business, with 2.2 GW installed of operational capacity in the Belgian North Sea.
- Active maintenance of those parks out of Port Oostende with crew transfer vessels and service operating vessels
- With more than 800 people directly employed in the O&M business for the offshore wind in Oostende.



* Green energy
entrepreneurs at heart.

EXTENSION BELGIAN MARINE SPATIAL PLAN

+3,6 GW
Installed 2030

New concession zone
for wind farms

221km²

at 35 km from the coast


Wind farms in the
Dutch part of the
North Sea

Operational and
planned wind farms

225km²

at 23 km from the coast

2,2 GW
Installed 2020



source: De Tijd / tijd.be / 21-04-2018

Crew Transfer Vessels

Infra - O & M



SOV (Service Operating Vessels) - hotelvessels

Infra - O & M




Reducing the carbon footprint of an offshore windfarm



- The O&M activities in the offshore wind industry have today a **considerable carbon footprint**
 - The vast majority of specialized vessels for offshore wind installation, operation and maintenance are driven by internal combustion engines, mainly using fossil fuel, for propulsion.
 - This is still the case for most of the recently build Crew Transfer Vessels (during the last 5 years), which will be in use for at least another 10 to 15 years
 - For CTVs the priorities are speed, reliability and safety of transfer, while incentives on CO2 emission reduction are low, and so far little or no requirements were imposed as permit requirement or as award criteria
- Our existing BE wind farms
 - We estimate that the O&M operations and maintenance logistics for the existing BE windfarms consume **7.5 - 9 million litre of diesel fuel per year, generating 20000 – 24000 tons of CO2** (approx. the equivalent of 3000 cars)
 - => average of 3500 to 4000 litre / year / MW of installed capacity





Figuur 5.1: Situering van de vier potentiële projectlocaties op een luchtfoto van de haven van Oostende met aanduiding van een perimeter van 115 m

Location






ISHY – Hydrogen Refuelling Station (HRS)



Status of the project

- Feasibility study:
 - ✓ Explore the potential future demand and related business model for hydrogen in the harbor of Oostende
 - ✓ Technical concept, safety screening for suitable locations, preferred location identified
- Realization of the facility:
 - ✓ Detailed engineering completed
 - ✓ Safety and implementation study completed
 - ✓ Permit (“Omgevingsvergunning”) awarded on 25.08.2022
 - ✓ Procurement, realization and testing – all contracts signed
 - Assembly of main components, civil works and construction of the HRS ongoing
- Planned capacity and phasing:
 - Phase 1: 600 kgH₂/day (**R&D project**), 4 vessels @150kg H₂/day
 - Phase 2: 1600 kgH₂/day, expected within 5 years, investment not part of R&D project
 - Phase 3: 3000 KgH₂/day, expected within 10 years, investment not part of R&D project





VER.	STATUS	VER. DATE	ISS.	REV.	APP.	DESCRIPTION
0.11	075	03/03/2022	KVN	DVA		Update
0.10	075	02/03/2022	KVN	DDE		Update
0.1	050	07/02/2022	KVN	DDE		FIRST DRAFT

PROJECT: ISHY PROJECT
OOSTENDE, ESPLANADESTRAAT


SUBJECT: HAKSEL INSTALLATION
3D - ISOMETRIC VIEW 1

Doc. name: H2-01-0001-3D-ISO-1-A4_0.11-075

 Parkwind Sint Maartenstraat 5 3000 Leuven • Belgium tel: +32 (0)16 240 790 www.parkwind.eu	ISSUED BY: KVN	REVIEWER: DVA	APPROVAL:	FORMAT: A4
	SCALE: 1: 125	INITIAL DATE: 07/02/2022	PROJECTION: 3d	



Dispenser – Refuelling a moving vessel



H2 refuelling station – Power installed



H2 Mass Flow 1544.648649 kg/day

H-Drive Parameters	Inlet Pressure (Bar)	Interstage (Bar)	Outlet Pressure (Bar)	Flowrate (Nm3/hr)	Flowrate (kg/hr)	Running Time (Hours)	Hyd Pressure (Bar)	Hyd Power (kW)	No. of Boosters	Hyd Power (kW)	Hyd Flow (l/min)	Process Cooling Required Per Booster (kW)	Total Process Cooling Required Per System (kW)
	99	308	500	357.2	32.18018018	24	248	73	2	146	140	37.8	60.48
	99	308	500	357.2	32.18018018	24	248	73	2	146	140	37.8	60.48
Average				357.2	32.18018018	24	248	73	2	146	140	37.8	60.48

	Maximum	Average Running	HPU Installed Power
Total Hydraulic Power (kW) / Running (kW)	146	97.3236	150 kW
Total Process HPU Cooling Required (Per HPU / Total)	20	40	
Total Process Cooling (kW)	100.48		Chiller Installed
Total Process Electrical Power Installed (kW) / Running (kW)	49.53004953	25.4	ICE 116 42 kW
Total Dispense Cooling Electrical Power (kW) / Running (kW)	0	0	0 kW

HPU TO Cooling:- 8 kW for 30 kW for 55 kW motor. 12/55 For 75 kW 16/75

CO2 Chiller Running

65

	Maximum Installed	Average Running	Maximum Running
Total Electrical Power Required (Installed / Running)	193.285	122.7236	195.5300495 kW
Safety Factor (10%)	212.6135	134.99596	215.0830545 kW
Total + Safety Factor (Installed / Running)	212.6135	134.99596	215.0830545 kW

150 kW Installed

Process Chillers

Hydraulic Power	1.512166797
Process Power	0.394652856
Dispense Power	0
Ancillaries	0.019965705
Total kWh/kg	1.926785358 kWh/kg Total (Running)

Model ICE		003	005	007	010	015	022	029	039	046	057	076	090	116	150	183	230	310	360
aircooled	Cooling capacity- kW	2,5	5,1	7,0	9,5	14,3	21,8	28,1	38,2	45,2	56,4	76,0	90,2	115,5	149,2	182,3	227,9	309,1	359,7
	Comp. abs. power- kW	0,70	1,40	2,0	2,27	3,43	5,19	5,66	7,69	10,1	12,3	15,4	20,3	24,9	30,8	40,1	51,4	46,4	81,5
	Cooling capacity- kW	1,8	3,8	5,2	7,0	10,6	16,2	20,8	28,4	33,8	42,1	56,5	67,1	86,4	110,9	135,4	165,3	223,7	259,1
watercooled	Comp. abs. power- kW	0,62	1,31	1,67	2,16	3,24	4,46	5,93	8,26	10,6	13,1	16,4	21,2	25,8	33,5	42,1	54,3	66,4	83,7
	Cooling capacity- kW							29,6	39,5	47,6	59,0	79,8	97,5	120,1	156,7	195,0			
	Comp. abs. power- kW							5,16	7,13	9,04	11,0	13,8	17,3	22,6	27,6	34,8	on request		
	Cooling capacity- kW							21,9	29,3	35,3	43,9	59,1	72,3	89,4	116,1	144,6	on request		
	Comp. abs. power- kW							5,17	7,17	8,93	11,1	13,9	17,0	22,8	27,8	34,4			
Compressors																			
Compt./circuits		1/1																	
Max abs. power - 1 comp. kW		0,7	1,5	2,0	3,0	4,3	6,9	7,8	11,1	13,7	16,8	11,1	13,7	16,8	11,1	13,7	16,8	23,3	28,7
Axial fans																			
Quantity		n°																	
Max abs. power - 1 fan kW		0,12	0,12	0,14	0,14	0,61	0,61	0,78	0,61	0,61	0,78	0,78	0,78	2,0	2,0	2,0	2,0	2,0	2,0
Air flow m³/h		2300	2300	4400	4100	7100	6800	9200	12400	12000	17400	25500	25000	26400	47000	46000	66000	88000	86000
Centrifugal fans																			
Quantity		n°																	
Max abs. power - 1 fan kW		N.A.																	
Air flow m³/h		on request																	
Head pressure kPa		on request																	
Water-cooled version																			
Condenser water flow- m³/h		N.A.																	
Connections (in/out)		on request																	

75 Kw Per booster – Total 150 Kw

50 Kw for the process chiller

10 Kw for ancillaries. – Air Compressor and PLC / Lights etc.

Total Installed 210 kW

HRS challenges



- Market
 - Very immature market and technology (hybrid marine propulsion), impossible to forecast
 - Many recently built CTVs, still using fossil fuel technology
 - Zero-emission difficult to achieve in offshore wind (speed and distance)
 - Lack of incentives on existing wind farms, requirements mostly on new projects

- Engineering first of a kind, no HRS experience in marine, higher quantity of H2
 - No H2 industry-standards in marine environments, difficult certification
 - Refueling a moving vessel laying at the quayside at 500bar pressure
 - Much higher quantity of H2 compared with road transport

- Permit first of a kind
 - Permit for the HRS was first of a kind for the local authorities
 - Safety / risk difficult to assess

- Withdrawal of GEOaqua
 - GEO withdrew from the project after all contracts for the HRS were signed, and after we had agreed a long-term use contract for GEO's hybrid vessel in our wind farms
 - Currently only 1 other hybrid vessel active in the port of Oostende

**CMB
.TECH**

**WINDCAT
WORKBOATS**



HYDROCAT



POWERED BY HYDROGEN

Interreg 
North-West Europe
H2SHIPS